### **Features**

- Low-voltage and Standard-voltage Operation
  - $-1.8v (V_{CC} = 1.8V to 3.6V)$
  - $-2.5v (V_{CC} = 2.5V to 5.5V)$
- Internally Organized 65,536 x 8
- Two-wire Serial Interface
- Schmitt Triggers, Filtered Inputs for Noise Suppression
- Bidirectional Data Transfer Protocol
- 1 MHz (2.5V, 5.5V), 400 kHz (1.8V) Compatibility
- Write Protect Pin for Hardware and Software Data Protection
- 128-byte Page Write Mode (Partial Page Writes Allowed)
- Self-timed Write Cycle (5 ms Max)
- High Reliability
  - Endurance: 1,000,000 Write Cycles
  - Data Retention: 40 Years
- Lead-free/Halogen-free Devices
- 8-lead PDIP, 8-lead JEDEC SOIC, 8-lead EIAJ SOIC, 8-lead TSSOP, 8-ball dBGA2, and 8-lead Ultra Thin Small Array (SAP) Packages
- Die Sales: Wafer Form, Waffle Pack and Bumped Die


## **Description**


The AT24C512B provides 524,288 bits of serial electrically erasable and programmable read only memory (EEPROM) organized as 65,536 words of 8 bits each. The device's cascadable feature allows up to eight devices to share a common two-wire bus. The device is optimized for use in many industrial and commercial applications where low-power and low-voltage operation are essential. The devices are available in space-saving 8-pin PDIP, 8-lead JEDEC SOIC, 8-lead EIAJ SOIC, 8-lead TSSOP, 8-ball dBGA2 and 8-lead Ultra Thin SAP packages. In addition, the entire family is available in 1.8V (1.8V to 3.6V) and 2.5V (2.5V to 5.5V) versions.


Table 0-1. Pin Configurations


Pin Name	Function
A0-A2	Address Inputs
SDA	Serial Data
SCL	Serial Clock Input
WP	Write Protect













# Two-wire Serial EEPROM

512K (65,536 x 8)

## AT24C512B

with Three Device Address Inputs

勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw

Rev. 5297A-SEEPR-1/08






## **Absolute Maximum Ratings\***

Operating Temperature	e55°C to +125°C
Storage Temperature	65°C to +150°C
Voltage on Any Pin with Respect to Ground	d1.0V to +7.0V
Maximum Operating Vo	oltage 6.25V
DC Output Current	5.0 mA

\*NOTICE:

Stresses beyond those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at these or any other conditions beyond those indicated in the operational sections of this specification is not implied. Exposure to absolute maximum rating conditions for extended periods may affect device reliability.

Figure 0-1. Block Diagram



勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw

WWW.100Y.

#### 1. **Pin Description**

SERIAL CLOCK (SCL): The SCL input is used to positive edge clock data into each EEPROM device and negative edge clock data out of each device.

SERIAL DATA (SDA): The SDA pin is bidirectional for serial data transfer. This pin is opendrain driven and may be wire-ORed with any number of other open-drain or open collector devices.

DEVICE/PAGE ADDRESSES (A2, A1, A0): The A2, A1, and A0 pins are device address inputs that are hardwired (directly to GND or to Vcc) for compatibility with other AT24Cxx devices. When the pins are hardwired, as many as eight 512K devices may be addressed on a single bus system. (Device addressing is discussed in detail under "Device Addressing," page 8.) A device is selected when a corresponding hardware and software match is true. If these pins are left floating, the A2, A1, and A0 pins will be internally pulled down to GND. However, due to capacitive coupling that may appear during customer applications, Atmel® recommends always connecting the address pins to a known state. When using a pull-up resistor, Atmel recommends using  $10k\Omega$  or less.

WRITE PROTECT (WP): The write protect input, when connected to GND, allows normal write operations. When WP is connected directly to Vcc, all write operations to the memory are inhibited. If the pin is left floating, the WP pin will be internally pulled down to GND. However, due to capacitive coupling that may appear during customer applications, Atmel recommends always connecting the WP pins to a known state. When using a pull-up resistor, Atmel recommends using  $10k\Omega$  or less.

WWW.100Y.COM.TW 特力材料886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www. 100y. com. tw

WWW.100Y.COM.





## 2. Memory Organization

**AT24C512B**, **512K SERIAL EEPROM**: The 512K is internally organized as 512 pages of 128-bytes each. Random word addressing requires a 16-bit data word address.

**Table 2-1.** Pin Capacitance<sup>(1)</sup>

Applicable over recommended operating range from:  $T_A = 25$ °C, f = 1.0 MHz,  $V_{CC} = +1.8$ V to +5.5V

Symbol	Test Condition	Max	Units	Conditions
C <sub>I/O</sub>	Input/Output Capacitance (SDA)	100 8 COM	pF	$V_{I/O} = 0V$
C <sub>IN</sub>	Input Capacitance (A <sub>0</sub> , A <sub>1</sub> , SCL)	N.100 6 COM	pF	V <sub>IN</sub> = 0V

Note: 1. This parameter is characterized and is not 100% tested.

Table 2-2. DC Characteristics

Applicable over recommended operating range from:  $T_{Al} = -40^{\circ}\text{C}$  to  $+85^{\circ}\text{C}$ ,  $V_{CC} = +1.8\text{V}$  to +5.5V (unless otherwise noted)

Symbol	Parameter	Test Condition	TOW.TW	Min	Тур	Max	Units
V <sub>CC1</sub>	Supply Voltage	WWW. 100X.COM.TW		1.8	001.001	3.6	V
V <sub>CC2</sub>	Supply Voltage	WW 10	OY.COM.TW	2.5	100 X	5.5	V
I <sub>cc</sub>	Supply Current	V <sub>CC</sub> = 5.0V	READ at 400 kHz	WW.	1007.00	2.0	mA
I <sub>cc</sub>	Supply Current	V <sub>CC</sub> = 5.0V	WRITE at 400 kHz	NW.	N.100Y.	3.0	mA
MAIN'S CONTRA		V <sub>CC</sub> = 1.8V	VI OOY. COLUMN	MAIN	W.100Y.	1.0	μΑ
I <sub>SB1</sub>	Standby Current	V <sub>CC</sub> = 3.6V	$V_{IN} = V_{CC} \text{ or } V_{SS}$	111	W.100Y	3.0	μΑ
I <sub>SB2</sub> Standby Current	Standby Current	V <sub>CC</sub> = 2.5V	VOV.	1	W.100	2.0	μA
	Standby Current	$V_{CC} = 5.5V$	$V_{IN} = V_{CC} \text{ or } V_{SS}$	N (	W.10	6.0	μA
I <sub>LI</sub>	Input Leakage Current	$V_{IN} = V_{CC} \text{ or } V_{S}$	s 1100 Y.COM.		0.10	3.0	μΑ
I <sub>LO</sub>	Output Leakage Current	V <sub>OUT</sub> = V <sub>CC</sub> or \	/ss	TW	0.05	3.0	μΑ
V <sub>IL</sub>	Input Low Level <sup>(1)</sup>	TW	T. T. WWW.160V.CO.		MMA	V <sub>CC</sub> x 0.3	V
V <sub>IH</sub>	Input High Level <sup>(1)</sup>	W.	MMM·In	V <sub>CC</sub> x 0.7	WW	V <sub>CC</sub> + 0.5	V
V <sub>OL1</sub>	Output Low Level	V <sub>CC</sub> = 1.8V	I <sub>OL</sub> = 0.15 mA	OM	WY	0.2	V
V <sub>OL2</sub>	Output Low Level	V <sub>CC</sub> = 3.0V	I <sub>OL</sub> = 2.1 mA	COMP.	W	0.4	V

Note: 1.  $V_{IL}$  min and  $V_{IH}$  max are reference only and are not tested.

勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw

WWW.100Y.COM.TW

**Table 2-3.** 

AC Characteristics (Industrial Temperature)

For recommended operating range from Test conditions. Applicable over recommended operating range from  $T_{Al} = -40$ °C to +85°C,  $V_{CC} = +1.8$ V to +5.5V, CL = 100 pF (unless otherwise noted). Test conditions are listed in Note 2.

	NWW.IOOV.COM.	to W	.8-volt	2.5, 5.0			
Symbol	Parameter	Min	Max	Min	Max	Units	
f <sub>SCL</sub>	Clock Frequency, SCL	· TW	400	WTW	1000	kHz	
t <sub>LOW</sub>	Clock Pulse Width Low	1.3	MAM. TOOX.CC	0.4		μs	
t <sub>HIGH</sub>	Clock Pulse Width High	0.6	WWW.TOUX.C	0.4		μs	
ti luca co	Noise Suppression Time <sup>(1)</sup>	OM	100	CONTRACTIV	50	ns	
t <sub>AA</sub>	Clock Low to Data Out Valid	0.05	0.9	0.05	0.55	μs	
t <sub>BUF</sub>	Time the bus must be free before a new transmission can start <sup>(1)</sup>	1.3	WWW.100	0.5	N	μs	
t <sub>HD.STA</sub>	Start Hold Time	0.6	01.WW.10	0.25		μs	
t <sub>SU.STA</sub>	Start Set-up Time	0.6	M MWW.1	0.25	I	μs	
t <sub>HD.DAT</sub>	Data In Hold Time	OON	NWW	100 ° CO	V.I.	μs	
t <sub>SU.DAT</sub>	Data In Set-up Time	100		100	M.I	ns	
t <sub>R</sub>	Inputs Rise Time <sup>(1)</sup>	1.100 Y. CON	0.3	W.100 E	0.3	μs	
t <sub>F</sub>	Inputs Fall Time <sup>(1)</sup>	W.1001.CO	300	M.100	100	ns	
t <sub>su.sто</sub>	Stop Set-up Time	0.6	M.I.A.	0.25	COM.	μs	
t <sub>DH</sub>	Data Out Hold Time	50	OWIT	50	COM.	ns	
t <sub>wr</sub>	Write Cycle Time	WW.1001.	5	MM.100	5	ms	
Endurance <sup>(1)</sup>	25°C, Page Mode, 3.3V	MMM.100	1,000,000	WWW.10	OOX.COM	Write Cycles	

R<sub>L</sub> (connects to V<sub>CC</sub>): 1.3 k $\Omega$  (2.5V, 5V), 10 k $\Omega$  (1.8V) Input pulse voltages: 0.3 V<sub>CC</sub> to 0.7 V Input rise and fall times: ≤ 50 ns

Input and output timing reference voltages: 0.5  $V_{\rm CC}$ 

WWW.100Y.COM.TW

特力材料886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 WWW.100Y.COM.TV Http://www. 100y. com. tw WWW.100Y.COM.TW





# 3. Device Operation

**CLOCK and DATA TRANSITIONS:** The SDA pin is normally pulled high with an external device. Data on the SDA pin may change only during SCL low time periods (see Figure 3-4 on page 8). Data changes during SCL high periods will indicate a start or stop condition as defined below.

**START CONDITION:** A high-to-low transition of SDA with SCL high is a start condition which must precede any other command (see Figure 3-5 on page 8).


**STOP CONDITION:** A low-to-high transition of SDA with SCL high is a stop condition. After a read sequence, the stop command will place the EEPROM in a standby power mode (see Figure 3-5 on page 8).

**ACKNOWLEDGE:** All addresses and data words are serially transmitted to and from the EEPROM in 8-bit words. The EEPROM sends a zero during the ninth clock cycle to acknowledge that it has received each word.

**STANDBY MODE:** The AT24C512B features a low power standby mode which is enabled: a) upon power-up and b) after the receipt of the STOP bit and the completion of any internal operations.

Software Reset: After an interruption in protocol, power loss or system reset, any 2-wire part can be protocol reset by following these steps: (a) Create a start bit condition, (b) clock 9 cycles, (c) create another start bit followed by stop bit condition as shown below. The device is ready for next communication after above steps have been completed.

Figure 3-1. Protocol Reset Condition



勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw

WWW.100Y.COM.

WWW.100Y.

Bus Timing (SCL: Serial Clock, SDA: Serial Data I/O) Figure 3-2.





Figure 3-3. Write Cycle Timing (SCL: Serial Clock, SDA: Serial Data I/O)

WWW.100Y.COM.TW

WWW.100Y.COM.




Note: 1. The write cycle time  $t_{WR}$  is the time from a valid stop condition of a write sequence to the end of the internal clear/write cycle. WWW.100Y.COM.T

WWW.100Y.COM.TW 勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 WWW.100 Y.COM.TW Http://www.100y.com.tw WWW.100Y.COM.TW







Figure 3-4. Data Validity



W.100X.COM.TW Figure 3-5. Stor Start and Stop Definition WWW.100Y.C WWW.100Y.COM.TW



Output Acknowledge Figure 3-6.



勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw

WWW.100Y.C

## 4. Device Addressing

The 512K EEPROM requires an 8-bit device address word following a start condition to enable the chip for a read or write operation (see Figure 6-1 on page 10). The device address word consists of a mandatory "1", "0" sequence for the first four most significant bits as shown. This is common to all two-wire EEPROM devices.

The 512K uses the three device address bits A2, A1, A0 to allow as many as eight devices on the same bus. These bits must compare to their corresponding hardwired input pins. The A2, A1 and A0 pins use an internal proprietary circuit that biases them to a logic low condition if the pins are allowed to float.

The eighth bit of the device address is the read/write operation select bit. A read operation is initiated if this bit is high and a write operation is initiated if this bit is low.

Upon a compare of the device address, the EEPROM will output a "0". If a compare is not made, the device will return to a standby state.

**DATA SECURITY:** The AT24C512B has a hardware data protection scheme that allows the user to Write Protect the whole memory when the WP pin is at  $V_{CC}$ .

## 5. Write Operations

BYTE WRITE: A write operation requires two 8-bit data word addresses following the device address word and acknowledgment. Upon receipt of this address, the EEPROM will again respond with a "0" and then clock in the first 8-bit data word. Following receipt of the 8-bit data word, the EEPROM will output a "0". The addressing device, such as a microcontroller, then must terminate the write sequence with a stop condition. At this time the EEPROM enters an internally-timed write cycle, t<sub>WR</sub>, to the nonvolatile memory. All inputs are disabled during this write cycle and the EEPROM will not respond until the write is complete (see Figure 6-2 on page 10).

**PAGE WRITE:** The 512K EEPROM is capable of 128-byte page writes.

A page write is initiated the same way as a byte write, but the microcontroller does not send a stop condition after the first data word is clocked in. Instead, after the EEPROM acknowledges receipt of the first data word, the microcontroller can transmit up to 127 more data words. The EEPROM will respond with a "0" after each data word received. The microcontroller must terminate the page write sequence with a stop condition (see Figure 6-3 on page 11).

The data word address lower 7 bits are internally incremented following the receipt of each data word. The higher data word address bits are not incremented, retaining the memory page row location. When the word address, internally generated, reaches the page boundary, the following byte is placed at the beginning of the same page. If more than 128 data words are transmitted to the EEPROM, the data word address will "roll over" and previous data will be overwritten. The address roll over during write is from the last byte of the current page to the first byte of the same page.

**ACKNOWLEDGE POLLING:** Once the internally-timed write cycle has started and the EEPROM inputs are disabled, acknowledge polling can be initiated. This involves sending a start condition followed by the device address word. The Read/Write bit is representative of the operation desired. Only if the internal write cycle has completed will the EEPROM respond with a "0", allowing the read or write sequence to continue.





## 6. Read Operations

Read operations are initiated the same way as write operations with the exception that the Read/Write select bit in the device address word is set to "1". There are three read operations: current address read, random address read and sequential read.

**CURRENT ADDRESS READ:** The internal data word address counter maintains the last address accessed during the last read or write operation, incremented by "1". This address stays valid between operations as long as the chip power is maintained. The address roll over during read is from the last byte of the last memory page, to the first byte of the first page.

Once the device address with the Read/Write select bit set to "1" is clocked in and acknowledged by the EEPROM, the current address data word is serially clocked out. The microcontroller does not respond with an input "0" but does generate a following stop condition (see Figure 6-4 on page 11).

**RANDOM READ:** A random read requires a "dummy" byte write sequence to load in the data word address. Once the device address word and data word address are clocked in and acknowledged by the EEPROM, the microcontroller must generate another start condition. The microcontroller now initiates a current address read by sending a device address with the Read/Write select bit high. The EEPROM acknowledges the device address and serially clocks out the data word. The microcontroller does not respond with a "0" but does generate a following stop condition (see Figure 6-5 on page 11).

**SEQUENTIAL READ:** Sequential reads are initiated by either a current address read or a random address read. After the microcontroller receives a data word, it responds with an acknowledge. As long as the EEPROM receives an acknowledge, it will continue to increment the data word address and serially clock out sequential data words. When the memory address limit is reached, the data word address will roll over and the sequential read will continue. The sequential read operation is terminated when the microcontroller does not respond with a "0" but does generate a following stop condition (see Figure 6-6 on page 11).

Figure 6-1. Device Address





Figure 6-2. Byte Write



Page Write Figure 6-3.




Figure 6-4. Current Address Read






Figure 6-5. Random Read



Sequential Read Figure 6-6.



勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www. 100y. com. tw



W.100Y.COM.TV



## **Ordering Information**

Ordering Code	Voltage	Package	Operation Range
T24C512B-PU (Bulk form only)	1.8	8P3	W
T24C512B-PU25 (Bulk form only)	2.5	8P3	
T24C512BN-SH-B <sup>(1)</sup> (NiPdAu Lead Finish)	1.8	8S1	
T24C512BN-SH-T <sup>(2)</sup> (NiPdAu Lead Finish)	1.8	8S1	
T24C512BN-SH25-B <sup>(1)</sup> (NiPdAu Lead Finish)	2.5	8S1	
T24C512BN-SH25-T <sup>(2)</sup> (NiPdAu Lead Finish)	2.5	8S1	
T24C512BW-SH-B <sup>(1)</sup> (NiPdAu Lead Finish)	1.8	8S2	
T24C512BW-SH-T <sup>(2)</sup> (NiPdAu Lead Finish)	1.8	8S2	Lead-free/Halogen-free/
T24C512BW-SH25-B <sup>(1)</sup> (NiPdAu Lead Finish)	2.5	8S2	Industrial Temperature
T24C512BW-SH25-T <sup>(2)</sup> (NiPdAu Lead Finish)	2.5	8S2	(-40°C to 85°C)
T24C512B-TH-B <sup>(1)</sup> (NiPdAu Lead Finish)	1.8	8A2	
T24C512B-TH-T <sup>(2)</sup> (NiPdAu Lead Finish)	1.8	8A2	
T24C512B-TH25-B <sup>(1)</sup> (NiPdAu Lead Finish)	2.5	8A2	
T24C512B-TH25-T <sup>(2)</sup> (NiPdAu Lead Finish)	2.5	8A2	
T24C512BY7-YH-T <sup>(2)</sup> (NiPdAu Lead Finish)	1.8	8Y7	
T24C512BY7-YH25-T <sup>(2)</sup> (NiPdAu Lead Finish)	2.5	8Y7	
T24C512BU2-UU-T <sup>(2)</sup>	1.8	8U2-1	
T24C512B-W-11 <sup>(3)</sup>	1.8	Die Sale	Industrial Temperature (-40°C to 85°C)

Notes: 1. "-B" denotes bulk

- 2. "-T" denotes tape and reel. SOIC = 4K per reel. TSSOP and dBGA2 = 5K per reel. SAP = 3K per reel. EIAJ = 2K per reel.
- 3. Available in tape and reel, and wafer form; order as SL788 for inkless wafer form. Bumped die available upon request. Please contact Serial Interface Marketing.

IN COM.							
TOO T COM'L							
100 F. COW.							
8-lead, 0.200" Wide Plastic Gull Wing Small Outline Package (EIAJ SOIC)							
8-lead, 4.4 mm Body, Plastic Thin Shrink Small Outline Package (TSSOP)							
8-lead, 6.00 mm x 4.90 mm Body, Ultra Thin, Dual Footprint, Non-leaded, Small Array Package (SAP)							
WW.100 P. C.							
WW.100 2							
M. 100 T							
W.100 F							

WWW.100Y.C

# Part marking scheme: 8-PDIP(1.8V)

### 7.1

	VWW		
7.1	8-PDIP(1.8V)		
TO	P MARK	Seal Year	Υ =
VW.100 T C		Seal Week	6:
WW.100 1.		MANITOR TO COMP.	7:
1,100 x	<u> </u>		8:
1007	A T M L	U Y W W	9:
WWW.	<u> </u>	-44][6]]	
WWW.10	2 F B	1 WWW. 100 Y. COM	
MMM	1-4-111	1425 Jan 1925 Con	
WWW.	* Lot Number	MMM. TOOX.CO	Lot
WWW	1101.COM.TM	WWW 100X.CC	вот
MM	Pin 1 Indicator	(Dot)	
MA			
7.2	8-PDIP(2.5V)		

Y =	SEAL	YEAR		WW	= :	SEAL '	WEEK
6:	2006	0:	2010	0:	2 =	Week	2
7:	2007	1:	2011	04	4 =	Week	4
8:	2008	2:	2012	1.1	: :	::::	:
9:	2009	3:	2013	MIN	: :	::::	::
				50	) =	Week	50
				5:	2 =	Week	52

Lot Number to Use ALL Characters in Marking

### BOTTOM MARK

WWW.100

WWW.100Y.COM.

No Bottom Mark WWW.100Y.C

#### 7.2 8-PDIP(2.5V)

.2	8-PDIP(2.5V)					
TOE	MARK		Seal	Yea	r	COY =
				Seal	Week	CO6:
					L.W.	100 2 (7:1
	44-  -0-	1-1-1	<u> </u>		-22	8:
	A T M L	U	Y	W	W	9:
	11-4-11-4-0	0[	-74			
	2 F B	2				
	[[[	-c9	7	-77	<sub>     </sub>	
	* Lot Number					Lot
	-+0		24/	7.11		
	WWW					BOTT
	Pin 1 Indicator	(Dot	)			

				NO	BOLL	om M	ar	K			
	Y =	SEAL	YEAR			WW =	= 5	SEAL	WEE	K	
ek (	6:	2006	0:	2010		02	(€	Week	2		
	7:	2007	1:	2011	WW	04	7	Week	4		
[ 100 x	8:	2008	2:	2012	N V	1.1:00	:	HO3	1:1		
	9:	2009	3:	2013	N. A.A.	OL V		1111	M		
WWW.						50	(7)	Week	50		
						52	ξņ	Week	52		
WWW.											
	Lot	Numbe	er to	Use	ALL	Char	ac	ters	in	Mark	ir

Lot Number to Use ALL Characters in Marking WW.100X.COM.

# BOTTOM MARK M.M. 1007. G

WW.100Y.COM.TW

COM.TW

Y.COM.TW

ov.com.TW

No Bottom Mark WWW.100Y.COM.TW WWW.100Y.COM.TW WWW.100Y.COM.TW

WWW.100Y.COM.TW 勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 WWW.Tooy.COM.TW Http://www.100y.com.tw WWW.100Y.COM.TW




WWW.100Y.COM



#### 8-SOIC(1.8V) 7.3

7.3	8-SOIC(	1.8V)							
TOP	MARK		Seal Year	Y =	SEAL	YEAR		WW = SEAL WE	EEK
			Seal Week	6:	2006	0:	2010	02 = Week 2	2
			ook.Com. tw	7:	2007	1:	2011	04 = Week 4	1
		[[+44	<del></del> 0    <sub></sub>	8:	2008	2:	2012	: : : : : : : : : : : : : : : : : :	:
	AT	M L H	Y W W	9:	2009	3:	2013		::
	[[324]		1-10171-241					50 = Week 5	50
	2 F	В 1						52 = Week 5	52
	[22][4]	Y  44Y	11 <del>-0</del> 211						
	* Lot	Number	MM. TOOX.COM	Lot	Numbe	r to	Use ALL	Characters	in Marking
	[===(0)/-1]		1441-140m						
	OM.			BOT	TOM MA	RK			
	Pin 1 In	dicator (Do	E) W 1007.				No Bott	tom Mark	

## 8-SOIC(2.5V)



WWW.100Y.COM.TW WWW.100Y.COM. 勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw WWW.100Y.COM.TW

WWW.100Y.COM.

WWW.100Y.C

## WWW.100Y.COM.TW 7.5 8-TSSOP(1.8V)

#### TOP MARK

7.5	8-TSSOP(1.8V)
TOI	P MARK
	Pin 1 Indicator (Dot)
	MAN TO THE WAY TO THE
	* H Y W W
	COM       0 X COM
2	CF B 1 * WWW. COM
WWW.I	-
WWW.Inc	ON COM. TW WWW.TOOY.COM.
BO	TTOM MARK

Y =	SEAL	YEAR		WW = SEAL WEER	Χ
6:	2006	0:	2010	02 = Week 2	
7:	2007	1;	2011	04 = Week 4	
8:	2008	2:	2012	::::::::	
9:	2009	3:	2013	M:: : :::: ::	
				50 = Week 50	
				52 = Week 52	
Coun	try of	rigin			

# Country of origin WWW.100Y.COM.TW WWW.100Y.COM.TW

WWW.100

WWW.100X.COM.

#### 8-TSSOP(2.5V) 7.6

#### TOP MARK

	Y =	SEAL	YEAR		WW =	= < 5	SEAL V	VEEK	
	6:	2006	0:	2010	02	=	Week	2	
	7:	2007	1:	2011	04	Œ	Week	4	
	8:	2008	2:	2012		1:0	0::::	M.	
	9:	2009	3:	2013	M.J.	:	90.A.Y	Y	
					50	=	Week	50	
					52	ā	Week	52	
EN MA	Cour	ntry of	origin						

W.100Y.COM.TW

WT.MO:

#### BOTTOM MARK

# Country of origin MMM.1007.Cg WWW.100Y.COM.TW


WWW.100Y.COM.TW 勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 WWW.nov.COM.TW Http://www.100y.com.tw WWW.100Y.COM.TW




WWW.100



#### 8-Ultra Thin SAP (1.8V) 7.7





WWW.100Y.COM.TW 勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw

WWW.100Y.COM.TW

WWW.100Y.C

WWW.100Y.COM.TW

WWW.100Y.C0

WWW.100Y.COM.TW

WWW.100Y.C

#### 7.8 dBGA2

```
100Y.COM.TW
                 TOP MARK
                                       WWW.100Y.COM.TW
                                               100X.COM.TW
                 LINE 1---->
                                  2FBU
                                      Pin 1 This Corner
                 LINE 2--
                                 YMTC
                                          WWW.100Y.COM.TW
                                 <---
                                          WWW.10
                 P = Country of Origin
                 Y = ONE DIGIT YEAR CODE
                                              WW.100Y.COM.TW
                 4: 2004 7: 2007
                 5: 2005
                          8: 2008
                 M = SEAL MONTH (USE ALPHA DESIGNATOR A-L)
A = JANUARY
B = FERRY
                                               WWW.100Y.COM.TW
                                                WWW.100Y.COM.TW
WWW.100Y.COM.TW
                  J = OCTOBER

K = NOVEY
                  - NOVEMBER
L = DECEMBER
                  K = NOVEMBER
   WWW.100Y.COM.T
     NUMBERS TO CORRESPOND
WITH ATK TRACE
                    TC = TRACE CODE (ATMEL LOT
                    WITH ATK TRACE CODE LOG BOOK)
```

WWW.100Y.C

WWW.100Y.COM.TW

WWW.100Y.COM.TW

WWW.100Y.

WWW.100Y.COM.TW

WWW.100Y.COM.TW

100Y.COM.TW

WWW.100

WWW.100Y.COM.

WWW.100Y.COM.TW 勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 WWW.100Y.COM.TW Http://www. 100y. com. tw WWW.100Y.COM.TW






## 8. Package Information

## U2-1 - dBGA2

勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787

Http://www.100y.com.tw



8U2-1, 8-ball, 2.35 x 3.73 mm Body, 0.75 mm pitch, Small Die Ball Grid Array Package (dBGA2)

TITLE

1150 E. Cheyenne Mtn. Blvd.

Colorado Springs, CO 80906


REV.

Α


DRAWING NO.

PO8U2-1


## **8P3 - PDIP**



Top View



**End View** 



### **COMMON DIMENSIONS**

(Unit of Measure = inches)

SYMBOL	MIN	NOM	MAX	NOTE
A	11.10	V.COD	0.210	2
A2	0.115	0.130	0.195	
b	0.014	0.018	0.022	5
b2	0.045	0.060	0.070	6
b3	0.030	0.039	0.045	6
С	0.008	0.010	0.014	TW
M D	0.355	0.365	0.400	3
D1	0.005	M-In	V.EO	3
E	0.300	0.310	0.325	4
E1	0.240	0.250	0.280	3
е		0.100 BSC	1001.	Mor
eA		0.300 BSC	100%	4
L	0.115	0.130	0.150	2

Notes:

- 1. This drawing is for general information only; refer to JEDEC Drawing MS-001, Variation BA, for additional information.
- 2. Dimensions A and L are measured with the package seated in JEDEC seating plane Gauge GS-3.
- 3. D, D1 and E1 dimensions do not include mold Flash or protrusions. Mold Flash or protrusions shall not exceed 0.010 inch.
- 4. E and eA measured with the leads constrained to be perpendicular to datum.
- 5. Pointed or rounded lead tips are preferred to ease insertion.
- 6. b2 and b3 maximum dimensions do not include Dambar protrusions. Dambar protrusions shall not exceed 0.010 (0.25 mm).

01/09/02




2325 Orchard Parkway San Jose, CA 95131 **TITLE 8P3**, 8-lead, 0.300" Wide Body, Plastic Dual In-line Package (PDIP)

DRAWING NO.	REV.
8P3	B







## 8S1 - JEDEC SOIC



Top View



Side View



**End View** 

## **COMMON DIMENSIONS** (Unit of Measure = mm)

SYMBOL	MIN	NOM	MAX	NOTE
Α	1.35	W. <del>1</del> 00	1.75	T. I.
A1	0.10	100 TAN	0.25	WIN
В	0.31	3110	0.51	MI
C	0.17	11 7	0.25	- N J
D	4.80	MIT.	5.00	On
E1	3.81	THE TAX	3.99	$CO_{Mr}$
) E	5.79	- <del>-</del>	6.20	COD
е		1.27 BSC	W.100	- c0
LIT	0.40	2///	1.27	17.0
Ø	0°	-4/1	8°	101.C.

Note: These drawings are for general information only. Refer to JEDEC Drawing MS-012, Variation AA for proper dimensions, tolerances, datums, etc.

10/7/03




1150 E. Cheyenne Mtn. Blvd. Colorado Springs, CO 80906 TITLE


WWW.100Y.

**8S1**, 8-lead (0.150" Wide Body), Plastic Gull Wing Small Outline (JEDEC SOIC)


DRAWING NO. 8S1 B

### 8S2 - EIAJ SOIC





## **END VIEW**



#### COMMON DIMENSIONS (Unit of Measure = mm)

SYMBOL	MIN	NOM	MAX	NOTE
Α	1.70	Too	2.16	
A1	0.05	N.100,	0.25	-31
b	0.35	W.100	0.48	5
С	0.15	100	0.35	5
D	5.13	N	5.35	TIM
E1	5.18	MM·r	5.40	2, 3
E	7.70	WW.	8.26	$CO_{Mr}$
ME	0.51	TINI	0.85	COM
θ	0°	- T	8°	CON
е		1.27 BSC	WI 100	4

## SIDE VIEW

- Notes: 1. This drawing is for general information only; refer to EIAJ Drawing EDR-7320 for additional information.
  - 2. Mismatch of the upper and lower dies and resin burrs aren't included.
  - 3. It is recommended that upper and lower cavities be equal. If they are different, the larger dimension shall be regarded.
  - 4. Determines the true geometric position.
  - 5. Values b,C apply to plated terminal. The standard thickness of the plating layer shall measure between 0.007 to .021 mm.

4/7/06



2325 Orchard Parkway San Jose, CA 95131 **TITLE 852**, 8-lead, 0.209" Body, Plastic Small Outline Package (EIAJ)


DRAWING NO. REV. 8S2 D




勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787




## **8A2 - TSSOP**



Top View



Side View



**End View** 

## **COMMON DIMENSIONS**

(Unit of Measure = mm)

SYMBOL	MIN	NOM	MAX	NOTE
D	2.90	3.00	3.10	2, 5
EN	V	6.40 BSC	on V.C	JA T
E1	4.30	4.40	4.50	3, 5
Α	_	WW	1.20	COM.
A2	0.80	1.00	1.05	COM
b T	0.19	1/1	0.30	4
е	N	0.65 BSC	10	N.C.
$C5_{\mu}$	0.45	0.60	0.75	JOY.Ce
L1	TIN	1.00 REF	MM	ON C

- Notes: 1. This drawing is for general information only. Refer to JEDEC Drawing MO-153, Variation AA, for proper dimensions, tolerances, datums, etc.
  - 2. Dimension D does not include mold Flash, protrusions or gate burrs. Mold Flash, protrusions and gate burrs shall not exceed 0.15 mm (0.006 in) per side.
  - 3. Dimension E1 does not include inter-lead Flash or protrusions. Inter-lead Flash and protrusions shall not exceed 0.25 mm
  - 4. Dimension b does not include Dambar protrusion. Allowable Dambar protrusion shall be 0.08 mm total in excess of the b dimension at maximum material condition. Dambar cannot be located on the lower radius of the foot. Minimum space between protrusion and adjacent lead is 0.07 mm.
  - 5. Dimension D and E1 to be determined at Datum Plane H.

5/30/02




2325 Orchard Parkway San Jose, CA 95131

TITLE 8A2, 8-lead, 4.4 mm Body, Plastic Thin Shrink Small Outline Package (TSSOP)

DRAWING NO.	REV.
8A2	В

### 8Y7 - UTSAP



1150 E. Cheyenne Mtn. Blvd. Colorado Springs, CO 80906 TITLE

WWW.100X.COM.;

 $\bf 8Y7,\,8\text{-lead}$  (6.00 x 4.90 mm Body) Ultra-Thin SOIC Array Package (UTSAP) Y7

0.50

3.81 REF

0.60

e1

DRAWING NO.

8Y7

REV. В




勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw

0.70



勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www. 100y. com. tw

### 8U2-1 - dBGA2



5. Dimension 'b' is measured at the maximum solder ball diameter.

This drawing is for general information only.

6/17/03

1150 E. Ohanana May Blad	TITLE.	DRAWING NO.	REV.
1150 E. Cheyenne Mtn. Blvd. Colorado Springs, CO 80906	8U2-1, 8-ball, 2.35 x 3.73 mm Body, 0.75 mm pitch, Small Die Ball Grid Array Package (dBGA2)	PO8U2-1	Α

WWW.100Y.

A<sub>2</sub>

b D

E

е

e1 d

d1

0.40

0.25

0.45

2.35 BSC

3.73 BSC 0.75 BSC

0.74 REF

0.75 BSC

0.80 REF

0.30 0.35

0.50

# WW.100Y.COM.TW **Revision History**

Doc. Rev.	Date	Comments
5297A	1/2008	AT24C512B product with date code 2008 work week 14 (814) or later supports 5Vcc operation Initial document release

WWW.100Y.COM.TW

MY.COM.TW

WWW.100Y.COM.7

WWW.100

WWW.100Y.COM.TW 勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www. 100y. com. tw

WWW.100Y.

WWW.100Y.COM.TW

ooy.COM.TW

