#### **Features**

- Compatible with MCS®51 Products
- 4K Bytes of Reprogrammable Flash Memory
  - Endurance: 1,000 Write/Erase Cycles
- . 2.7V to 6V Operating Range
- Fully Static Operation: 0 Hz to 24 MHz
- Two-level Program Memory Lock
- 128 x 8-bit Internal RAM
- 15 Programmable I/O Lines
- Two 16-bit Timer/Counters
- Six Interrupt Sources
- Programmable Serial UART Channel
- Direct LED Drive Outputs
- On-chip Analog Comparator
- Low-power Idle and Power-down Modes
- Brown-out Detection
- Power-On Reset (POR)
- Green (Pb/Halide-free/RoHS Compliant) Packaging

## 1. Description

The AT89C4051 is a low-voltage, high-performance CMOS 8-bit microcontroller with 4K bytes of Flash programmable and erasable read-only memory. The device is manufactured using Atmel's high-density nonvolatile memory technology and is compatible with the industry-standard MCS-51 instruction set. By combining a versatile 8-bit CPU with Flash on a monolithic chip, the Atmel AT89C4051 is a powerful microcontroller which provides a highly-flexible and cost-effective solution to many embedded control applications.

The AT89C4051 provides the following standard features: 4K bytes of Flash, 128 bytes of RAM, 15 I/O lines, two 16-bit timer/counters, a five-vector, two-level interrupt architecture, a full duplex serial port, a precision analog comparator, on-chip oscillator and clock circuitry. In addition, the AT89C4051 is designed with static logic for operation down to zero frequency and supports two software-selectable power saving modes. The Idle Mode stops the CPU while allowing the RAM, timer/counters, serial port and interrupt system to continue functioning. The power-down mode saves the RAM contents but freezes the oscillator disabling all other chip functions until the next hardware reset.





# 8-bit Microcontroller with 4K Bytes Flash


# AT89C4051






## 2. Pin Configuration

#### 2.1 PDIP/SOIC



勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw

## 3. Block Diagram



## 4. Pin Description

4.1 VCC

Supply voltage.

4.2 GND

Ground.

勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw

#### 4.3 Port 1

Port 1 is an 8-bit bi-directional I/O port. Port pins P1.2 to P1.7 provide internal pullups. P1.0 and P1.1 require external pullups. P1.0 and P1.1 also serve as the positive input (AIN0) and the negative input (AIN1), respectively, of the on-chip precision analog comparator. The Port 1 output buffers can sink 20 mA and can drive LED displays directly. When 1s are written to Port 1 pins, they can be used as inputs. When pins P1.2 to P1.7 are used as inputs and are externally pulled low, they will source current ( $I_{II}$ ) because of the internal pullups.

Port 1 also receives code data during Flash programming and verification.

#### 4.4 Port 3

Port 3 pins P3.0 to P3.5, P3.7 are seven bi-directional I/O pins with internal pullups. P3.6 is hard-wired as an input to the output of the on-chip comparator and is not accessible as a general-purpose I/O pin. The Port 3 output buffers can sink 20 mA. When 1s are written to Port 3 pins they are pulled high by the internal pullups and can be used as inputs. As inputs, Port 3 pins that are externally being pulled low will source current (I<sub>II</sub>) because of the pullups.

Port 3 also serves the functions of various special features of the AT89C4051 as listed below:

Port Pin	Alternate Functions
P3.0	RXD (serial input port)
P3.1	TXD (serial output port)
P3.2	ĪNTO (external interrupt 0)
P3.3	INT1 (external interrupt 1)
P3.4	T0 (timer 0 external input)
P3.5	T1 (timer 1 external input)

Port 3 also receives some control signals for Flash programming and verification.

#### 4.5 RST

Reset input. All I/O pins are reset to 1s as soon as RST goes high. Holding the RST pin high for two machine cycles while the oscillator is running resets the device.

Each machine cycle takes 12 oscillator or clock cycles.

#### 4.6 XTAL1

Input to the inverting oscillator amplifier and input to the internal clock operating circuit.





#### 4.7 XTAL2


Output from the inverting oscillator amplifier.

#### 5. Oscillator Characteristics

XTAL1 and XTAL2 are the input and output, respectively, of an inverting amplifier which can be configured for use as an on-chip oscillator, as shown in Figure 5-1. Either a quartz crystal or ceramic resonator may be used. To drive the device from an external clock source, XTAL2 should be left unconnected while XTAL1 is driven as shown in Figure 5-2. There are no requirements on the duty cycle of the external clock signal, since the input to the internal clocking circuitry is through a divide-by-two flip-flop, but minimum and maximum voltage high and low time specifications must be observed.


Figure 5-1. Oscillator Connections

勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw



Note: C1, C2 = 30 pF  $\pm$  10 pF for Crystals = 40 pF  $\pm$  10 pF for Ceramic Resonators

Figure 5-2. External Clock Drive Configuration



# 6. Special Function Registers

A map of the on-chip memory area called the Special Function Register (SFR) space is shown in the Table 6-1.

Note that not all of the addresses are occupied, and unoccupied addresses may not be implemented on the chip. Read accesses to these addresses will in general return random data, and write accesses will have an indeterminate effect.

User software should not write 1s to these unlisted locations, since they may be used in future products to invoke new features. In that case, the reset or inactive values of the new bits will always be 0.

Table 6-1. AT89C4051 SFR Map and Reset Values

	JO COM.		VIV.100	OM		N.19			
0F8H	TOON COM	TN N	MAN. 1007.	COWITY	WIN	W.100 Y.C	M.T.		OFF
0F0H	B 00000000	LTV \	MMM.100	Y.COM.TY	N W	AM.100X.C	OM.TW	1	0F7
DE8H	M.100X.C	OM.TW	MMM.10	ON.COM.T		1.M.M. 100.	COM.T	N	0E
E0H	ACC 00000000	COW.TW	MMM	100 X.CO.N	TW	MMM:10	N.COM.		0E
DBH	MMM:100	L.CON.TW	WW	N.100X.CO	M.TW	WWW.	OOX.COD	LTW	0D
DD0H	PSW 00000000	OY.COM.TY		AN.100X.C	OM.TW	WWW	N.100X'CO	M.TW	0D
DC8H	MMM.	100X.COM.T		1.1.100,	.COM.TW	MA	M.100X.	ONITA	0CI
OC0H	WWW	W.100X.COM	TW	WWW.100	Y.COM.TY	N N	MM: 700	COM.TW	0C
DB8H	IP XXX00000	IN.100X.CO	M.TW	WMM.	OOX.COM	LM	WWW.10	OY.COM.T	0В
OBOH	P3 11111111	VWW.100Y.C	OM.TW	WWV	1.100 X COV	VI.TW	MMMI	100X COM	0B
H8AC	IE 0XX00000	MMM.100X	COMITW	MA	M:100X.C	M.TW	MANA	100 X CO	0A
H0AC		WWW.100	V.COM.T	N N	M.M.100X.	COM.TW	W	W.100X.C	0A
98H	SCON 00000000	SBUF XXXXXXXX	OOX.COM	IM.	MMM.100	V.COM.TV	N V	MM.TOOX.	9FI
90H	P1 11111111	WWW	1.100 X.CON	U.TW	WWW.10	OX.COM.	W	MMM.100	971
88H	TCON 00000000	TMOD 00000000	TL0 00000000	TL1 00000000	TH0 00000000	TH1 00000000	T.L.M.	WWW.10	8F
80H		SP 00000111	DPL 00000000	DPH 00000000	MM	N.100X.CC	M.TW	PCON 0XXX0000	87I



勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw



#### 7. Restrictions on Certain Instructions

The AT89C4051 is an economical and cost-effective member of Atmel's growing family of microcontrollers. It contains 4K bytes of Flash program memory. It is fully compatible with the MCS-51 architecture, and can be programmed using the MCS-51 instruction set. However, there are a few considerations one must keep in mind when utilizing certain instructions to program this device.

All the instructions related to jumping or branching should be restricted such that the destination address falls within the physical program memory space of the device, which is 4K for the AT89C4051. This should be the responsibility of the software programmer. For example, LJMP 0FE0H would be a valid instruction for the AT89C4051 (with 4K of memory), whereas LJMP 1000H would not.

#### 7.1 Branching Instructions

LCALL, LJMP, ACALL, AJMP, SJMP, JMP @A+DPTR. These unconditional branching instructions will execute correctly as long as the programmer keeps in mind that the destination branching address must fall within the physical boundaries of the program memory size (locations 00H to FFFH for the 89C4051). Violating the physical space limits may cause unknown program behavior.

CJNE [...], DJNZ [...], JB, JNB, JC, JNC, JBC, JZ, JNZ. With these conditional branching instructions the same rule above applies. Again, violating the memory boundaries may cause erratic execution.

For applications involving interrupts, the normal interrupt service routine address locations of the 80C51 family architecture have been preserved.

## 7.2 MOVX-related Instructions, Data Memory

The AT89C4051 contains 128 bytes of internal data memory. Thus, in the AT89C4051 the stack depth is limited to 128 bytes, the amount of available RAM. External DATA memory access is not supported in this device, nor is external Program memory execution. Therefore, no MOVX [...] instructions should be included in the program.

A typical 80C51 assembler will still assemble instructions, even if they are written in violation of the restrictions mentioned above. It is the responsibility of the controller user to know the physical features and limitations of the device being used and adjust the instructions used correspondingly.

## 8. Program Memory Lock Bits

On the chip are two lock bits which can be left unprogrammed (U) or can be programmed (P) to obtain the additional features listed in the Table 8-1.

勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw

**Table 8-1.** Lock Bit Protection Modes<sup>(1)</sup>

Pro	gram Lock	Bits	WWW. 100X.CO.
WWW.	LB1	LB2	Protection Type
1,171	100 UCO	UVITVU	No program lock features
2	10PI.CU	MIVU	Further programming of the Flash is disabled
3	RY.C	P	Same as mode 2, also verify is disabled

Note: 1. The Lock Bits can only be erased with the Chip Erase operation.

#### 9. Idle Mode

In idle mode, the CPU puts itself to sleep while all the on-chip peripherals remain active. The mode is invoked by software. The content of the on-chip RAM and all the special functions registers remain unchanged during this mode. The idle mode can be terminated by any enabled interrupt or by a hardware reset.

P1.0 and P1.1 should be set to "0" if no external pullups are used, or set to "1" if external pullups are used.

勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw It should be noted that when idle is terminated by a hardware reset, the device normally resumes program execution, from where it left off, up to two machine cycles before the internal reset algorithm takes control. On-chip hardware inhibits access to internal RAM in this event, but access to the port pins is not inhibited. To eliminate the possibility of an unexpected write to a port pin when Idle is terminated by reset, the instruction following the one that invokes Idle should not be one that writes to a port pin or to external memory.


#### 10. Power-down Mode

In the power-down mode the oscillator is stopped and the instruction that invokes power-down is the last instruction executed. The on-chip RAM and Special Function Registers retain their values until the power-down mode is terminated. The only exit from power-down is a hardware reset. Reset redefines the SFRs but does not change the on-chip RAM. The reset should not be activated before  $V_{CC}$  is restored to its normal operating level and must be held active long enough to allow the oscillator to restart and stabilize.

P1.0 and P1.1 should be set to "0" if no external pullups are used, or set to "1" if external pullups are used.

## 11. Brown-out Detection

When  $V_{CC}$  drops below the detection threshold, all port pins (except P1.0 and P1.1) are weakly pulled high. When  $V_{CC}$  goes back up again, an internal Reset is automatically generated after a delay of typically 15 msec. The nominal brown-out detection threshold is 2.1V  $\pm$  10%.



勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw





## 12. Programming The Flash

The AT89C4051 is shipped with the 4K bytes of on-chip PEROM code memory array in the erased state (i.e., contents = FFH) and ready to be programmed. The code memory array is programmed one byte at a time. Once the array is programmed, to re-program any non-blank byte, the entire memory array needs to be erased electrically.

**Internal Address Counter:** The AT89C4051 contains an internal PEROM address counter which is always reset to 000H on the rising edge of RST and is advanced by applying a positive going pulse to pin XTAL1.

**Programming Algorithm:** To program the AT89C4051, the following sequence is recommended.

特力材料886-3-5753170

胜特力电子(上海) 86-21-34970699

胜特力电子(深圳) 86-755-83298787

Http://www.100y.com.tw

- Power-up sequence: Apply power between VCC and GND pins Set RST and XTAL1 to GND
- 2. Set pin RST to "H" Set pin P3.2 to "H"
- 3. Apply the appropriate combination of "H" or "L" logic levels to pins P3.3, P3.4, P3.5, P3.7 to select one of the programming operations shown in the PEROM Programming Modes table.

To Program and Verify the Array:

- 4. Apply data for Code byte at location 000H to P1.0 to P1.7.
- 5. Raise RST to 12V to enable programming.
- 6. Pulse P3.2 once to program a byte in the PEROM array or the lock bits. The byte-write cycle is self-timed and typically takes 1.2 ms.
- 7. To verify the programmed data, lower RST from 12V to logic "H" level and set pins P3.3 to P3.7 to the appropriate levels. Output data can be read at the port P1 pins.
- 8. To program a byte at the next address location, pulse XTAL1 pin once to advance the internal address counter. Apply new data to the port P1 pins.
- 9. Repeat steps 6 through 8, changing data and advancing the address counter for the entire 4K bytes array or until the end of the object file is reached.
- 10. Power-off sequence: set XTAL1 to "L" set RST to "L" Turn V<sub>CC</sub> power off

Data Polling: The AT89C4051 features Data Polling to indicate the end of a write cycle. During a write cycle, an attempted read of the last byte written will result in the complement of the written data on P1.7. Once the write cycle has been completed, true data is valid on all outputs, and the next cycle may begin. Data Polling may begin any time after a write cycle has been initiated.

**Ready/Busy:** The Progress of byte programming can also be monitored by the RDY/BSY output signal. Pin P3.1 is pulled low after P3.2 goes High during programming to indicate BUSY. P3.1 is pulled High again when programming is done to indicate READY.

**Program Verify:** If lock bits LB1 and LB2 have not been programmed code data can be read back via the data lines for verification:

- 1. Reset the internal address counter to 000H by bringing RST from "L" to "H".
- 2. Apply the appropriate control signals for Read Code data and read the output data at the port P1 pins.
- 3. Pulse pin XTAL1 once to advance the internal address counter.
- 4. Read the next code data byte at the port P1 pins.
- 5. Repeat steps 3 and 4 until the entire array is read.

The lock bits cannot be verified directly. Verification of the lock bits is achieved by observing that their features are enabled.

**Chip Erase:** The entire PEROM array (4K bytes) and the two Lock Bits are erased electrically by using the proper combination of control signals and by holding P3.2 low for 10 ms. The code array is written with all "1"s in the Chip Erase operation and must be executed before any non-blank memory byte can be re-programmed.

**Reading the Signature Bytes:** The signature bytes are read by the same procedure as a normal verification of locations 000H, 001H, and 002H, except that P3.5 and P3.7 must be pulled to a logic low. The values returned are as follows.

(000H) = 1EH indicates manufactured by Atmel

(001H) = 41H indicates AT89C4051

勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw

## 13. Programming Interface

Every code byte in the Flash array can be written and the entire array can be erased by using the appropriate combination of control signals. The write operation cycle is self-timed and once initiated, will automatically time itself to completion.

Most major worldwide programming vendors offer support for the Atmel AT89 microcontroller series. Please contact your local programming vendor for the appropriate software revision.

## 13.1 Flash Programming Modes

Mode	W.100.	COM.	RST/V <sub>PP</sub>	P3.2/PROG	P3.3	P3.4	P3.5	P3.7
Write Code Data <sup>(1)(3)</sup>	M.100	A'COM'	12V	MAN TO COM	YN L	WHW.	OOX.COM	H
Read Code Data <sup>(1)</sup>	WW.	OOX.COM	TWH	WWW.100 Y.COM	TWL	WENN	100H.CO	M.H
Mais I all	MAN	Bit - 1	12V	WWW.CO	M.TW	HAM	W.100X.C	OMITY COMITY
Write Lock	MA	Bit - 2	12V	M (1/100 x C	OM.TW	Н	MM 100 x	COM!
Chip Erase	N	WW.100	12V	(2)	COM.T	N L	MAKN'I	OA. COL
Read Signature Byte		MAN WILL	HMIT	H.WW.100	N.CDM.	L	L	L

Notes: 1. The internal PEROM address counter is reset to 000H on the rising edge of RST and is advanced by a positive pulse at XTAL1 pin.

- 2. Chip Erase requires a 10-ms PROG pulse.
- 3. P3.1 is pulled Low during programming to indicate RDY/BSY.





Figure 13-1. Programming the Flash Memory





Figure 13-2. Verifying the Flash Memory

WW.100Y.COM.TW



WWW.100Y.COM.TW

WWW.100Y

# 14. Flash Programming and Verification Characteristics


 $T_A = 20^{\circ}C$  to  $30^{\circ}C$ ,  $V_{CC} = 5.0 \pm 10\%$ 

Symbol	Parameter	Min	Max	Units
V <sub>PP</sub>	Programming Enable Voltage	11.5	12.5	V
I <sub>PP</sub>	Programming Enable Current	1001.COM.TW	250	μΑ
t <sub>DVGL</sub>	Data Setup to PROG Low	1.0		μs
t <sub>GHDX</sub>	Data Hold after PROG	1.0		μs
t <sub>EHSH</sub>	P3.4 (ENABLE) High to V <sub>PP</sub>	1.0		μs
t <sub>SHGL</sub>	V <sub>PP</sub> Setup to PROG Low	WW. Too COM 10		μs
t <sub>GHSL</sub>	V <sub>PP</sub> Hold after PROG	WW. CONTO		μs
t <sub>GLGH</sub>	PROG Width	WWW.to	110	μs
t <sub>ELQV</sub>	ENABLE Low to Data Valid	MMM.rook.COM	1.0	μs
t <sub>EHQZ</sub>	Data Float after ENABLE	MMM.TOOX.COM	1.0	μs
t <sub>GHBL</sub>	PROG High to BUSY Low	MAMAT 100X.COM	50	ns
t <sub>WC</sub>	Byte Write Cycle Time	MMM. 100X.CO.	2.0	ms
t <sub>BHIH</sub>	RDY/BSY\ to Increment Clock Delay	1.0	WIW	μs
t <sub>IHIL</sub>	Increment Clock High	200	OM.TW	ns

Note: 1. Only used in 12-volt programming mode.

## 15. Flash Programming and Verification Waveforms

勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw





# 16. Absolute Maximum Ratings\*

Operating Temperature	55°C to +125°C
Storage Temperature	65°C to +150°C
Voltage on Any Pin with Respect to Ground	1.0V to +7.0V
Maximum Operating Voltage	6.6V
DC Output Current	25.0 mA

\*NOTICE

Stresses beyond those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at these or any other conditions beyond those indicated in the operational sections of this specification is not implied. Exposure to absolute maximum rating conditions for extended periods may affect device reliability.

勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw

## 17. DC Characteristics

 $T_A = -40$ °C to 85°C,  $V_{CC} = 2.7$ V to 6.0V (unless otherwise noted)

Symbol	Parameter	Condition	Min	Max	Units
V <sub>IL</sub>	Input Low-voltage	DOX.COM.TW WWW.10	-0.5	0.2 V <sub>CC</sub> - 0.1	V
V <sub>IH</sub>	Input High-voltage	(Except XTAL1, RST)	0.2 V <sub>CC</sub> + 0.9	V <sub>CC</sub> + 0.5	V
V <sub>IH1</sub>	Input High-voltage	(XTAL1, RST)	0.7 V <sub>CC</sub>	V <sub>CC</sub> + 0.5	V
V <sub>OL</sub>	Output Low-voltage <sup>(1)</sup> (Ports 1, 3)	$I_{OL} = 20 \text{ mA}, V_{CC} = 5V$ $I_{OL} = 10 \text{ mA}, V_{CC} = 2.7V$	N.100X.COM	0.5	V
MI	N.100Y.COM.TW	$I_{OH} = -80 \ \mu A, \ V_{CC} = 5V \pm 10\%$	2.4	U.I.	V
V <sub>OH</sub>	Output High-voltage (Ports 1, 3)	I <sub>OH</sub> = -30 μA	0.75 V <sub>CC</sub>	W.T.	V
V	N.M.100 S.COM.T.W	I <sub>OH</sub> = -12 μA	0.9 V <sub>CC</sub>	OM. TW	V
I <sub>IL</sub>	Logical 0 Input Current (Ports 1, 3)	V <sub>IN</sub> = 0.45V	MMM.100X.	-50	μA
I <sub>TL</sub>	Logical 1 to 0 Transition Current (Ports 1, 3)	$V_{IN} = 2V, V_{CC} = 5V \pm 10\%$	MMM.100	-750	μA
I <sub>LI</sub>	Input Leakage Current (Port P1.0, P1.1)	0 < V <sub>IN</sub> < V <sub>CC</sub>	WWW.10	±10	μΑ
V <sub>OS</sub>	Comparator Input Offset Voltage	V <sub>CC</sub> = 5V	MMW.	20	√ mV
V <sub>CM</sub>	Comparator Input Common Mode Voltage	WWW.100Y.COM.TW	0	V <sub>cc</sub>	V
RRST	Reset Pulldown Resistor	WWW.100 COM.	50	300	ΚΩ
C <sub>IO</sub>	Pin Capacitance	Test Freq. = 1 MHz, T <sub>A</sub> = 25°C	W WY	10 CO	pF
	MMM.Ton	Active Mode, 12 MHz, V <sub>CC</sub> = 6V/3V	W WT	15/5.5	mA
I <sub>cc</sub>	Power Supply Current	Idle Mode, 12 MHz, V <sub>CC</sub> = 6V/3V P1.0 & P1.1 = 0V or V <sub>CC</sub>	M.TW Y	5/1	mA
	Devices device Mada(2)	V <sub>CC</sub> = 6V, P1.0 & P1.1 = 0V or V <sub>CC</sub>	N. TVI	20	μА
	Power-down Mode <sup>(2)</sup>	V <sub>CC</sub> = 3V, P1.0 & P1.1 = 0V or V <sub>CC</sub>	ONL.	5	μΑ

Notes: 1. Under steady state (non-transient) conditions, I<sub>OL</sub> must be externally limited as follows:


Maximum I<sub>OL</sub> per port pin: 20 mA

Maximum total  $I_{OL}$  for all output pins: 80 mA

If  $I_{OL}$  exceeds the test condition,  $V_{OL}$  may exceed the related specification. Pins are not guaranteed to sink current greater than the listed test conditions.

2. Minimum V<sub>CC</sub> for Power-down is 2V.

## 18. External Clock Drive Waveforms



WWW.100Y.COM

#### 19. External Clock Drive

	COM. TW WWW.	$V_{CC} = 2.7V \text{ to } 6.0V$		$V_{\rm CC}$ = 4.0V to 6.0V		
Symbol	Parameter	Min	Max M	Min	Max	Units
1/t <sub>CLCL</sub>	Oscillator Frequency	OCOM	12 W	W. 10001.CO	24	MHz
t <sub>CLCL</sub>	Clock Period	83.3	WE.	41.6	WIW	ns
t <sub>chcx</sub>	High Time	30	WI.IV	15	W.TW	ns
t <sub>CLCX</sub>	Low Time	30	OM.TW	1500	OW.TW	ns
t <sub>CLCH</sub>	Rise Time	WWW.TOOX.C	20	WW.100Y.	20	ns
t <sub>chcL</sub>	Fall Time	MM 100X.	20	MM. 1003	20	ns
	MAN TOOK CONTLAN	WW.100Y	COM.TW	MAIN 100	COMITW	-
			Y.COM.TW	WW.10	OY. COM.TW	T
			OY.COM.TW	勝特力材	料 886-3-57531	70

WWW.100Y.COM.

特力材料886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787

Http://www. 100y. com. tw

WWW.100X.CON




## 20. Serial Port Timing: Shift Register Mode Test Conditions


 $V_{CC}$  = 5.0V  $\pm$  20%; Load Capacitance = 80 pF

	WWW.TOOY.COM.TW	12 MHz Osc		Variable		
Symbol	Parameter	Min	Max	Min	Max	Units
t <sub>XLXL</sub>	Serial Port Clock Cycle Time	1.0	100 X . CO.	12t <sub>CLCL</sub>		μs
t <sub>QVXH</sub>	Output Data Setup to Clock Rising Edge	700	.100 1.	10t <sub>CLCL</sub> -133		ns
t <sub>XHQX</sub>	Output Data Hold after Clock Rising Edge	50	N.100 r.	2t <sub>CLCL</sub> -117		ns
t <sub>XHDX</sub>	Input Data Hold after Clock Rising Edge	0	W.100 1	0		ns
t <sub>XHDV</sub>	Clock Rising Edge to Input Data Valid	ON SAI	700	COM	10t <sub>CLCL</sub> -133	ns

## 21. Shift Register Mode Timing Waveforms




# 22. AC Testing Input/Output Waveforms<sup>(1)</sup>



勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw

Note: 1. AC Inputs during testing are driven at V<sub>CC</sub> - 0.5V for a logic 1 and 0.45V for a logic 0. Timing measurements are made at V<sub>IH</sub> min. for a logic 1 and V<sub>IL</sub> max. for a logic 0.


# 23. Float Waveforms<sup>(1)</sup>




Note: 1. For timing purposes, a port pin is no longer floating when a 100 mV change from load voltage occurs. A port pin begins to float when 100 mV change from the loaded V<sub>OH</sub>/V<sub>OL</sub> level occurs.

## 24. I<sub>CC</sub> (Active Mode) Measurements


特力材料886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www. 100y. com. tw



# 25. I<sub>CC</sub> (Idle Mode) Measurements



# 26. I<sub>CC</sub> (Power Down Mode) Measurements



1. XTAL1 tied to GND Notes:

2. P.1.0 and P1.1 =  $V_{CC}$  or GND

3. Lock bits programmed





## 27. Ordering Information

勝 特 力 材 料 886-3-5753170 胜特力电子(上海) 86-21-34970699 胜特力电子(深圳) 86-755-83298787 Http://www.100y.com.tw

#### 27.1

Speed (MHz)	Power Supply	Ordering Code	Package	Operation Range
OOY.CO	10 0 7// +- 0 0//	AT89C4051-12PC AT89C4051-12SC	20P3 20S	Commercial (0°C to 70°C)
12 2.7V to 6.0V	AT89C4051-12PI AT89C4051-12SI	20P3 20S	Industrial (-40°C to 85°C)	
24 4.0V to 6.0V	COMATY	AT89C4051-24PC AT89C4051-24SC	20P3 20S	Commercial (0°C to 70°C)
	AT89C4051-24PI AT89C4051-24SI	20P3 20S	Industrial (-40°C to 85°C)	

### 27.2 Green Package Option (Pb/Halide-free)


peed VIHz)	Power Supply	Ordering Code	Package	Operation Range
12	2.7V to 6.0V	AT89C4051-12PU AT89C4051-12SU	20P3 20S	Industrial (-40°C to 85°C)
24	4.0V to 6.0V	AT89C4051-24PU AT89C4051-24SU	20P3 20S	Industrial (-40°C to 85°C)


	Packa	ige Type	ANN 100 TV
20P3	20-lead, 0.300" Wide, Plastic Dual In-line Packa	age (PDIP)	N.
20S	20-lead, 0.300" Wide, Plastic Gull Wing Small C	Outline (SOIC)	7


EWW.100Y.CON.TW

## 28. Package Information

#### 28.1 20P3 - PDIP







Notes:

- 1. This package conforms to JEDEC reference MS-001, Variation AD.
- Dimensions D and E1 do not include mold Flash or Protrusion. Mold Flash or Protrusion shall not exceed 0.25 mm (0.010").

# COMMON DIMENSIONS

(Unit of Measure = mm)

SYMBOL	MIN	NOM	MAX	NOTE
Α	77	W.700	5.334	TA
A1	0.381	-100	7.0	1.1.
D	24.892	- <del>- 1</del> 10	26.924	Note 2
EN	7.620	- XX 1	8.255	MIT
E1	6.096	M.M.	7.112	Note 2
В	0.356	MAIN	0.559	COP
B1	1.270	V <del>E</del> W	1.551	COA
COL	2.921	-WV	3.810	$^{K}CO_{M}$
COM	0.203	-	0.356	V.CO
eB	- <del></del>	-	10.922	ov CC
eC	0.000	_	1.524	10 x
е	2.540 TYP			100 1.

1/23/04

20P3, 20-lead (0.300"/7.62 mm Wide) Plastic Dua	
Inline Package (PDIP)	ual

DRAWING NO. 20P3


D

REV.





#### **20S - SOIC** 28.2





#### **Atmel Corporation**

2325 Orchard Parkway San Jose, CA 95131, USA Tel: 1(408) 441-0311

Fax: 1(408) 487-2600

#### Regional Headquarters

#### Europe

Atmel Sarl Route des Arsenaux 41 Case Postale 80 CH-1705 Fribourg Switzerland

Tel: (41) 26-426-5555 Fax: (41) 26-426-5500

#### Asia

Room 1219 Chinachem Golden Plaza 77 Mody Road Tsimshatsui East Kowloon Hong Kong

Tel: (852) 2721-9778 Fax: (852) 2722-1369

#### Japan

9F, Tonetsu Shinkawa Bldg. 1-24-8 Shinkawa Chuo-ku, Tokyo 104-0033 Japan

Tel: (81) 3-3523-3551 Fax: (81) 3-3523-7581

#### **Atmel Operations**

#### Memory

2325 Orchard Parkway San Jose, CA 95131, USA Tel: 1(408) 441-0311 Fax: 1(408) 436-4314

#### Microcontrollers

2325 Orchard Parkway San Jose, CA 95131, USA Tel: 1(408) 441-0311 Fax: 1(408) 436-4314

La Chantrerie BP 70602 44306 Nantes Cedex 3, France Tel: (33) 2-40-18-18-18

# Fax: (33) 2-40-18-19-60 *ASIC/ASSP/Smart Cards*

Zone Industrielle 13106 Rousset Cedex, France Tel: (33) 4-42-53-60-00

Fax: (33) 4-42-53-60-01

1150 East Cheyenne Mtn. Blvd. Colorado Springs, CO 80906, USA

Tel: 1(719) 576-3300 Fax: 1(719) 540-1759

Scottish Enterprise Technology Park Maxwell Building East Kilbride G75 0QR, Scotland

Tel: (44) 1355-803-000 Fax: (44) 1355-242-743

#### RF/Automotive

Theresienstrasse 2 Postfach 3535 74025 Heilbronn, Germany Tel: (49) 71-31-67-0 Fax: (49) 71-31-67-2340

1150 East Cheyenne Mtn. Blvd. Colorado Springs, CO 80906, USA

Tel: 1(719) 576-3300 Fax: 1(719) 540-1759

Biometrics/Imaging/Hi-Rel MPU/ High Speed Converters/RF Datacom

Avenue de Rochepleine

BP 123

38521 Saint-Egreve Cedex, France

Tel: (33) 4-76-58-30-00 Fax: (33) 4-76-58-34-80

Literature Requests www.atmel.com/literature

Disclaimer: The information in this document is provided in connection with Atmel products. No license, express or implied, by estoppel or otherwise, to any intellectual property right is granted by this document or in connection with the sale of Atmel products. EXCEPT AS SET FORTH IN ATMEL'S TERMS AND CONDITIONS OF SALE LOCATED ON ATMEL'S WEB SITE, ATMEL ASSUMES NO LIABILITY WHATSOEVER AND DISCLAIMS ANY EXPRESS, IMPLIED OR STATUTORY WARRANTY RELATING TO ITS PRODUCTS INCLUDING, BUT NOT LIMITED TO, THE IMPLIED WARRANTY OF MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE, OR NON-INFRINGEMENT. IN NO EVENT SHALL ATMEL BE LIABLE FOR ANY DIRECT, INDIRECT, CONSEQUENTIAL, PUNITIVE, SPECIAL OR INCIDENTAL DAMAGES (INCLUDING, WITHOUT LIMITATION, DAMAGES FOR LOSS OF PROFITS, BUSINESS INTERRUPTION, OR LOSS OF INFORMATION) ARISING OUT OF THE USE OR INABILITY TO USE THIS DOCUMENT, EVEN IF ATMEL HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGES. Atmel makes no representations or warranties with respect to the accuracy or completeness of the contents of this document and reserves the right to make changes to specifications and product descriptions at any time without notice. Atmel does not make any commitment to update the information contained herein. Atmel's products are not intended, authorized, or warranted for use as components in applications intended to support or sustain life.

© Atmel Corporation 2005. All rights reserved. Atmel<sup>®</sup>, logo and combinations thereof, Everywhere You Are<sup>®</sup> and others, are registered trademarks or trademarks of Atmel Corporation or its subsidiaries. Other terms and product names may be trademarks of others.

